Deep rounded brick portal — R03

15 October 2026 · 352 Front Street West, Unit 105 / customer entrance 348 Front Street West

Status: reference translation and proposed form/material study. No measured layout, selected product, construction detail, permit approval or contractor quotation is issued.

What the new images clarify

The eight owner-supplied screenshots establish a **deep, substantial-looking portal/short tunnel**, with a relatively flattened crown, generously rounded upper corners, broad piers and continuous brick walls/soffit. The depth is central to its character. The earlier R02 front-only arch sketch did not adequately express that volume.

Root visually reviewed all eight images in chat and recorded REF01–REF08 in SRC-07. Original screenshot binaries are not available as local files; the observation-record hash does not claim to hash those originals. Image captions are reference content. No shop identity, building dimensions, masonry structure, brick product or fixing method has been independently established.

Translation for this restaurant

• Shape the forward-projecting enclosed kitchen and curved cashier as one quiet brick composition, with an opaque backing that conceals kitchen activity. The opening is a reception composition; it does not become a public route through the kitchen.

• Keep a compact opening in relation to the broad piers, with deep side returns and soffit. The proposed V02 image corrects V01's excessively long bar/window proportions. Neither version fixes dimensions or proves fit.

• Retain the warm irregular clay-brick appearance and restrained light joints; settle actual brick colour/texture/joints by physical samples under the intended lighting. A picture is not a product specification.

• Use the reference's grey mineral backdrop and restrained light to support the brick. Keep the owner's concrete-look floor **flush and continuous**: do not import brick floor returns, raised thresholds or steps from the retail reference.

• Preserve the separate guest-right corridor. Refrigeration remains two coolers plus one freezer, with relocation to the owner-confirmed LEFT wall to be coordinated separately; no reference-shop display cases are introduced.

• Finish the projected volume's upper surface for the view from the mezzanine. The rendered cap is only a visual suggestion; a measured top view/section and maintenance/support detail are still required. It is not a walking deck or storage area.

What the visualization does and does not resolve

The current proposed image is **R03_V02_Compact_Form_Study.png**. It is an AI-generated object/form study informed by the root's interpretation of the references; it is not a photograph of the restaurant or a view from a measured CAD model. It demonstrates the intended brick depth, rounded opening, compact curved counter, grey opaque backing and flush concrete-look floor.

It does not resolve staff working depth/entry, pickup/service access, an accessible transaction arrangement, sightlines, the actual guest corridor, floor/wall heights, arch support, kitchen fire/hygiene enclosure, full top finish or services. No staff aisle, clear width or headroom is certified. The right side of the image must not be read as a designed corridor. Do not fabricate or price the complete assembly from this image.

The existing mezzanine, required kitchen enclosure/ceiling and decorative brick support remain separately coordinated assemblies. The reference does not justify full masonry overhead or adhesive-only brick slips above people. The withdrawn curved brick upper-mezzanine ceiling edge remains excluded.

The ground universal WC remains in the current coordination baseline. Owner-desired storage conversion/added upstairs WC remains a separate conditional scenario. This reference study changes neither

that position nor current construction status.

Next measured issue

Use A5 as the owner-confirmed latest working reference, with its recorded dimension discrepancy and unverified City acceptance intact. Set out the actual kitchen front, cashier, independent corridor and retained WC route together. Survey portal available width/depth/height, counter working/access envelopes, the existing TV-fascia/mezzanine edge and upper sightline before choosing the real profile/radii.

Develop front elevation, plan, longitudinal/transverse section and a view from the mezzanine from the **same verified geometry**. Show support/enclosure, opaque screen, staff entry, service/pickup interface, accessible transaction, maintenance access and surface terminations. Deep piers/soffits use space and may affect the owner's 120-degree cashier visibility target; the reference does not prove that target.

R02 material unit allowances remain broad, unquoted comparisons only. No new quantity, complete canopy price, supplier approval or capital total is introduced by R03. The owner-reported approximately CAD 102,000+tax HVAC/ecology/gas figure and the missing quotation status are unchanged. Obtain a coordinated support/finish proposal and reconcile its scope once with existing packages.

R03 / COMPACT BRICK PORTAL - PROPOSED APPEARANCE

Deep rounded opening, substantial piers, curved cashier and opaque kitchen backing.



AI-GENERATED FORM STUDY | NOT A SITE LAYOUT | Staff access, transaction, circulation and dimensions unresolved